0

N121098 Wyo Proj

Sheets

# SINGLE BARREL 20'-0" X 12'-0"

# CONCRETE BOX CULVERT

# STA 13+55

## DEER CROSSING UNDERPASS

## SAGE JUNCTION EAST

N121098

LINCOLN COUNTY

## **PRELIMINARY**

### **GENERAL NOTES**

SPECIFICATIONS: WYDOT Standard Specifications for Road and Bridge Construction, 2010 Edition.

**DIMENSIONS**: Longitudinal dimensions are along flow line. Slopes are vertical: horizontal.

REINFORCING STEEL: Ensure reinforcing steel conforms to ASTM A 615 (Grade 60) for all bars, including ties and stirrups. Concrete cover to face of reinforcing steel is 2" unless noted. Dimensions for bent bars are out to out. Ensure bars marked with an asterisk (\*) are coated.

BAR MARKS Straight Bars Bent Bars - Designation Size –

EYEBOLTS: Use galvanized bar conforming to ASTM A 709 (Grade 36). Work necessary for the eyebolts is incidental to the contract pay item Class A

WEEP HOLE ASSEMBLIES: Work necessary for the weep hole assemblies is incidental to the contract pay item Class A Concrete.

PREFORMED EXPANSION JOINT FILLER: Work necessary for the preformed expansion joint filler is incidental to the contract pay item Class A Concrete.

CULVERT EXCAVATION: The estimated quantity of culvert excavation is 3060 CY and is incidental to the contract pay item Class A Concrete.

CULVERT SUBEXCAVATION: The bottom limits of culvert subexcavation is 3'-0" below the bottom of the culvert. Line the bottom of the culvert subexcavation with geotextile material separation. Backfill with pit run subbase conforming to grading J. The estimated quantity of culvert subexcavation is calculated in accordance with Stanard Plan 206-1, Culvert and Trench Excavation.

CULVERT BOTTOM BACKFILL: Backfill the bottom of the culvert with 2'-0"± of excavated material from the adjacent highway embankment. Work necessary for backfilling is incidental to the contract pay item Class A

BRIDGE OFFICE NOTIFICATION: The engineer will notify the State Bridge Engineer in writing within 14 calendar days after work has been completed at this structure.

## **DESIGN DATA**

SPECIFICATIONS: AASHTO LRFD Bridge Design Specifications, 8th Edition.

ADT: 1945 (Year 2005)

LOADING:

Live Load: HL93

Lateral live load surcharge: 2 ft earth or 72 psf

Dead Load: Design fill: 2.0 ft

(1) Vertical earth pressure: 120 pcf Lateral earth pressure: 36 pcf (2) Vertical earth pressure: 120 pcf Lateral earth pressure: 72 pcf

REINFORCED CONCRETE: Load and Resistance Factor Design -

Class A Concrete  $f'_{c} = 4000 \text{ psi}$ 

Reinforcing Steel  $f_v = 60,000 \text{ psi (Grade 60)}$ 

APPROACH ROADWAY WIDTH: 40'-0"

## **REFERENCES**

Supplementary Specifications:

Adjustment for Structural Steel SS-500G Structural Concrete with Quality Control and Quality Acceptance

Standard Plans:

206-1A Culvert and Trench Excavation

#### STRUCTURE NO. LFN

ML12B, RM 30.05 SEC 7, T21N, R119W

			_						
	WYO	OMING	DEPARTMEN	Γ OF	TRANSPORTATI	ON			
BRIDGE PROGRAM									
REVISIONS									
				T	\! Cti	I M Na	_		
REVIEW		DESIGN_	BBB , GG	ᆕĽ	esign Section	L M NO	)		
		DETAIL _			rwg No. P-000	6 Sheet	1	οf	2
APPROVAL		QTY'S _	✓	_I -	7 Wg No. F-000	Jileet		Oi	_

ESTIMATED QUANTITIES - CODE 08					
ITEM NO.	ITEM		TOTAL QUANTITY	ESTIMATE	
206.03300	CULVERT SUBEXCAVATION	CY	Х		
212.03900	PERVIOUS BACKFILL MATERIAL	CY	Х		
217.01025	GEOTEXTILE, MATERIAL SEPARATION (NON-WOVEN)		X		
301.01010	PIT RUN SUBBASE	CY	X		
503.01000	BRIDGE RAILING	FT	X		
513.00005	CLASS A CONCRETE	LS	LUMP SUM	X CY	
514.00015	REINFORCING STEEL	LS	LUMP SUM	X LB	
900.60000	CONTRACTOR QUALITY CONTROL (CONCRETE)	LS	LUMP SUM		

ECTIMATED QUANTITIES CODE OF


ection

0

Prelimina

4.01

Example



N121098\_1pl2.dgn

N121098 Wyo Proj

B1 of B6 Sheets

# SINGLE BARREL 20'-0" X 12'-0"

# CONCRETE BOX CULVERT

# STA 13+55

## DEER CROSSING UNDERPASS

## SAGE JUNCTION EAST

N121098

**CULVERT SUBEXCAVATION** 

PIT RUN SUBBASE

**CLASS A CONCRETE** 

REINFORCING STEEL

BRIDGE RAILING

PERVIOUS BACKFILL MATERIAL

GEOTEXTILE, MATERIAL SEPARATION (NON-WOVEN)

CONTRACTOR QUALITY CONTROL (CONCRETE)

## LINCOLN COUNTY

## **GENERAL NOTES**

**ESTIMATED QUANTITIES - CODE 08** 

SPECIFICATIONS: WYDOT Standard Specifications for Road and Bridge Construction, 2010 Edition.

<u>DIMENSIONS</u>: Longitudinal dimensions are along flow line. Slopes are vertical: horizontal.

REINFORCING STEEL: Ensure reinforcing steel conforms to ASTM A 615 (Grade 60) for all bars, including ties and stirrups. Concrete cover to face of reinforcing steel is 2" unless noted. Dimensions for bent bars are out to out. Ensure bars marked with an asterisk (\*) are coated.



EYEBOLTS: Use galvanized bar conforming to ASTM A 709 (Grade 36). Work necessary for the eyebolts is incidental to the contract pay item Class A

WEEP HOLE ASSEMBLIES: Work necessary for the weep hole assemblies is incidental to the contract pay item Class A Concrete.

ITEM NO.

206.03300

212.03900

217.01025

301.01010

503.01000

513.00005

514.00015

900.60000

PREFORMED EXPANSION JOINT FILLER: Work necessary for the preformed expansion joint filler is incidental to the contract pay item Class A Concrete.

<u>CULVERT EXCAVATION</u>: The estimated quantity of culvert excavation is 3060 CY and is incidental to the contract pay item Class A Concrete.

<u>CULVERT SUBEXCAVATION</u>: The bottom limits of culvert subexcavation is 3'-0" below the bottom of the culvert. Line the bottom of the culvert subexcavation with geotextile material separation. Backfill with pit run subbase conforming to grading J. The estimated quantity of culvert subexcavation is calculated in accordance with Stanard Plan 206-1, Culvert and Trench Excavation.

CULVERT BOTTOM BACKFILL: Backfill the bottom of the culvert with 2'-0"± of excavated material from the adjacent highway embankment. Work necessary for backfilling is incidental to the contract pay item Class A Concrete.

BRIDGE OFFICE NOTIFICATION: The engineer will notify the State Bridge Engineer in writing within 14 calendar days after work has been completed at this structure.

**ESTIMATE** 

268.7 CY

55,880 LB

TOTAL

QUANTITY

20

20

310

110

44

LUMP SUM

LUMP SUM

LUMP SUM

UNIT

CY

SY

CY

FT

LS

LS

## **DESIGN DATA**

SPECIFICATIONS: AASHTO LRFD Bridge Design Specifications,

ADT: 1945 (Year 2005)

LOADING:

Live Load: HL93

Lateral live load surcharge: 2 ft earth or 72 psf

Dead Load: Design fill: 2.0 ft

(1) Vertical earth pressure: 120 pcf Lateral earth pressure: 36 pcf (2) Vertical earth pressure: 120 pcf Lateral earth pressure: 72 pcf

REINFORCED CONCRETE: Load and Resistance Factor Design -

Class A Concrete f'<sub>c</sub> = 4000 psi

Reinforcing Steel  $f_v = 60,000 \text{ psi (Grade 60)}$ 

APPROACH ROADWAY WIDTH: 40'-0"

### REFERENCES

Supplementary Specifications:

Adjustment for Structural Steel SS-500G Structural Concrete with Quality

Control and Quality Acceptance

Standard Plans:

Culvert and Trench Excavation

#### STRUCTURE NO. LFN

ML12B, RM 30.05 SEC 7, T21N, R119W

		/				
WYOMING DEPARTMENT OF TRANSPORTATION						
BRIDGE PROGRAM						
REVISIONS						
		1				
REVIEW	DESIGN	Design Section L M Nop				
	DETAIL BBB J GGG	0006				
APPROVAL	QTY'S	Drwg No. 0006	Sheet 1 of 6			


ection

0

eneral


Note

Example




Example

N121098\_1cu2.dgn



Example



0

Example

